How Much Will That Trail Cost?

Jeff Weinstein Mike Sherrod Noel Fearon Derik Perez

8810

Trails and Greenways Conference

May 11, 2007

Costs

Cost to Plan (environmental, design)
Cost to Build
Cost to Operate
Cost to Maintain

Unknowns

Changes in Project Scope Changes in Material Costs Changes in Schedules / Timing Changes in Management / Administration

HOW MUCH WILL THAT TRAIL COST?

NOEL J. FEARON Associates Inc. Construction Cost Consultants 23323 Los Codona Avenue, Torrance, CA 90505-3715 E-mail : NJFA@earthlink.net

Trail construction cost factors:

- 1.1 Materials: Highway and trail construction material costs have increased disproportionately over recent year
 - Fuel costs affect delivery of materials to sometimes remote sites
 - Heavy equipment costs (steel, fuel, tires) are a higher proportion of trail and highway costs than other construction types
 - Asphalt costs have risen dramatically
 - Stone and gravel costs affected by fuel and equipment cost increases
 - Attached graph shows changes in producer price index for highway and street construction materials versus other construction types

■1.2 Labor: Construction labor costs have been more moderate over recent years; 3%-5% p.a.

- Labor resources for prevailing wage contractors have been tight in recent years, in common with construction generally
- Drop-off in residential construction volume in 2006-2007 not likely to benefit highway/trail construction resources & costs to any significant degree.

1.3 Market factors: Heavy demand for all construction resources in California over recent years.

- Drop-off in residential construction likely to be picked up by non-residential and public construction spending over the next few years.
- In a tight market, a project that is well designed and clearly defined will attract more and better bids and result in lower bid costs. In particular, avoid :
 - Confusion, discrepancies, contradictions in scope or design of the project
 - Excessive or confusing alternate cost packages (add or deduct)
 - Unrealistically tight construction period

Preparing budget cost estimates for grant applications

2.1 Scope:

Clearly define the scope of the project - how many feet/miles of trail, location and limits of construction areas, temporary and permanent fences, mitigation of damage to wildlife areas and habitats

2.2 Quantities: Calculate approximate quantities of typical trail components:

- Site prep. and grading Cu. Yards
- Trail surface and base materials Sq. Ft.
- Curbs & edgings Lin. Ft.
- Fences and gates Lin. Ft. & count for gates
- Storm water drainage usually site specific; catch basins, SD piping and trenching, storm water detention basins, outfalls and headwalls
- Trail lighting and power outlets if required per lighting standard; include for trench, conduit and wiring to power source

(continued on next slide...)

2.2 continued...

- Drinking water fountains include piping and trenching from point of connection
- Retaining walls Lin. Ft. & Sq. Ft.; minimize if possible
- Planting and irrigation Sq. Ft.
- Mitigation of damage to wildlife areas and habitats site specific
- General Contractor management and fee
- Soft costs design, construction management, permits

2.3 Pricing: Sources of unit pricing:

- Means Site Work & Landscape Cost Data 2007 - www.rsmeans.com/ bookstore/ detail.asp?sku=65287
- Caltrans Contract Cost Data download at www.dot.ca.gov/hq/esc/oe/awards/ (very large files!)
- Professional construction cost consultant


2.4 Allowances & markups: Add 15%-20% contingency for unforeseen items in early stage estimates; less at later,

better defined stages

Include an allowance for anticipated construction cost escalation to the anticipated mid-point of the construction period. Currently we recommend 8%-10% p.a.

Changes in PPIs for Construction Types

(12-Month Change through Month Shown)



City of Folsom Parks & Recreation Department

Urban Bike Trail Maintenance

Presenter: Derik Perez, Park & Trails Planner I Phone: 916-355-7345 E-Mail: <u>dperez@folsom.ca.us</u>

City of Folsom Bike Trails

- We currently have 32 miles of Class I bike trails;
- We've received \$5.1 million dollars in grant funding...and counting.
- We have 35 bike/ pedestrian bridges;
- We have 5 bicycle undercrossings;
- 20 miles of proposed Class I bike trails to construct;
- 10 kiosks;
- 1 Mountain Bike Skills Park;
- 1 BMX Park;
- 30 Bike Lockers;
- And 25 dog stations.

How we maintain our bike trails...

- 1. **City Maintenance Crews** (Work Orders, Emergencies, Installation of Signs, etc.)
- 2. Contractual (Weeding, Edging, Pruning, Blowing)
- Prison Labor (Weed abatement, fire breaks, retaining wall install, kiosk install, bench install, etc.)
- 4. **Service Groups** (trash pick-up, shrub planting, tree planting, etc.)
- 5. Volunteers (Mulch install, bridge maintenance, tree planting, etc.)
- 6. Adopt-a-trail Program (trash pick-up once a month)

Maintaining the trails...







What does bike trail maintenance consist of?

- Weed Control (Shoulders)
- Leaf Blowing
- Tree Maintenance/ Pruning
- Sweeping Debris & Erosion
- Vector Control
- Sign Maintenance/ Installation
- Graffiti Removal
- Retaining Wall Repair
- Staining of wood structures
- Erosion Control

Examples...







Examples cont...







How do we monitor trail maintenance?

- Residents (Walking, Cycling, Running, etc.)
- Maintenance Staff
- Bike Commuters
- Service Groups
- Routine Inspections (Weekly, Monthly, Bi-Annual, etc.)

Trail Maintenance Budget

1. General Fund

- a. \$41,600 current trail maintenance budget for FY 06/07
- b. Approximately \$1,600 / mile for bike trail maintenance for the Fiscal Year was estimated.
- c. This budget does not include any substantial repairs.

2. Estimating Budget

Budget is estimated at how many trails are anticipated to be development in the upcoming fiscal year based on previous year averages.

3. Renovation Projects

- a. \$350,000 is allocated each FY for Park and Trail Renovation Projects.
- b. The adopted "Parks & Recreational Facilities Renovation Master Plan" was adopted by City Council in May 2003.
- c. Renovation Funds are collected from Cell Tower revenue and deposited into a account which is accrued for Future Renovation Projects.

Trails – Estimated Useful Life

RENOVATION MASTER PLAN 2003 TRAILS: USEFUL LIFE & ESTIMATED COSTS

ardscaping (Trail Surfaces)	M-ti-l-/Di-ti	116-11-15-	Unit Date -
Items	Materials/Description	Useful Life	Unit Price
Bike Trails (class I)	(Generally 10 Feet Wide)		
Asphalt Resurfacing/Chip Seal	Resurface asphalt surface w/ Chip Seal & center line striping	10 years	\$ 0.50 \$
Asphalt Overlay	1" overlay of asphalt w/ centerline striping	20 years	\$13
Concrete	Removal and replacement	50 years	\$73
Decomposed Granite (DG)	Replacement of D.G	5 years	\$15
Aggregate Sub-base (AB)		6 years	\$33
Concrete Containment Curb		50 years	\$ 15
arking Lot			
Items	Materials/Description	Useful Life	Unit Price
Asphalt Overlay	1" Overlay of asphalt, repair, restripe & paint handicap logo	20 years	\$ 1.50 \$
Lighting	Poles and lighting fixtures	30 years	\$1,500 8
ructures			
Items	Materials/Description	Useful Life	Unit Price
Concrete Undercrossings	Complete Replacement	50 years	\$ 150
Concrete Bridges	Complete Replacement	50 years	\$ 400
Wood Bridges	Complete Replacement	20 years	\$ 500
Steel Bridges/overcrossings	Complete Replacement	30 years	\$ 750
Boardwalk	Complete Replacement	20 years	\$ 400
Replace wood Deck	Steel frame bridge with wooden deck	20 years	\$ 100
te Equipment / Furniture (Support F	acilities)		
Items	Materials/Description	Useful Life	Unit Price
Doggie Stations	Complete Replacement	15 years	\$ 1,200 8
Benches	Custom: Recycled Plastic with cobble siding	15 years	\$ 1,200
Barrier Posts	6" x 6" pressure treated posts	15 years	\$12
Bike Lockers	Metal lockers - 2 bikes per locker	10 years	\$350
Kiosks	Redwood structure, cobble base, with composite shingle roof	15 years	\$ 2000
Trash Cans	Metal container w/ concrete base	15 years	\$ 500 8
encing			
Items	Materials/Description	Useful Life	Unit Price
Tubular Steel	Painted black - similar to wrought iron	20	\$ 40
Post & Cable	4 x 4 x 6 wooden posts & metal cable	15	\$ 10

Site Specific Inventory

	TRAILS RENOVATION	INVENT	ORY	2002-200	03								
Map Number	Trail Name	Quantity/ SF	Miles	Year Built / Installed	Current Age	Condition	Priority	Price per unit	Total Costs	Estimated Useful Life	Last Renovation	Next Scheduled Renovation	7/2003-6/2004
12	Humbug • Willow Creek Trail	4	7.76	95/96/98/02	8/7/5/1	G/G/G/N	1/2/3/8						
	Proposed		10.20										
	Total Miles		17.96										
_	Hardscaping (Trail Surfaces)												
	Items												
	Lighting												
	Bike Trails (class I)	05.040.05	1.00	1995	8	0		# 0.50 OF	\$47,520	10		2005	
	Asphalt Resurfacing / Chip Seal	95,040 SF	1.80 1.80	1995	8	Good Good		\$ 0.50 SF \$ 1 SF		20		2005	
	Asphalt Overlay Asphalt Resurfacing / Chip Seal	95,040 SF 105,600 SF	2.00	1995	8	Good		\$ 0.50 SF	\$95,040 \$52,800	 10		2015	
		105,600 SF	2.00	1996	7	Good		\$ 0.50 SF \$ 1 SF	\$52,800	20		2006	
	Asphalt Overlay Asphalt Resurfacing / Chip Seal	105,600 SF	2.00	1996	5	Good		\$ 0.50 SF	\$83,640	 10		2016	
	Asphalt Resonating / Chip Sear	137,280 SF	2.60	1998	5	Good		\$1SF		20		2008	
	Asphalt Resurfacing / Chip Seal	73,920 SF	2.60	2002	1	New		\$ 0.50 SF	\$36,960	10		2018	
<u> </u>	Asphalt Overlay	73,920 SF 73,920 SF	1.40	2002	1	New		\$1SF	\$73,920	20		2012	
	Proposed Trails	75,520 31	1.40	2002		14800		φισι 	φι3,320	20		2022	
	Asphalt Resurfacing / Chip Seal	132,000 SF	2.50	2004	0	Proposed		\$ 0.50 SF	\$66,000	10		2014	
<u> </u>	Asphalt Resurfacing / Chip Seal	105,600 SF	2.00	2004		Proposed		\$ 0.50 SF	\$52,800	10		2014	
	Asphalt Resurfacing / Chip Seal	132.000 SF	2.50	2003	0	Proposed		\$ 0.50 SF	\$66,000	10		2013	
	Asphalt Resurfacing / Chip Seal	168,960 SF	3.20	2007	n n	Proposed		\$ 0.50 SF	\$84,480	10		2017	
<u> </u>	Asphalt Overlay	100,000 01	0.20	2000				↓ 0.00 OI		10		2010	
<u> </u>	Concrete												
<u> </u>	Decomposed Granite (DG)												
	Aggregate Sub-base (AB)												

Trails – Division Summary

	RENOVATION MASTER PLAN 2003 Trail Cost Projection																02/03 - 07/08
Sheet Number		Description	# of Bridges	# of Boardwalks	# of Overcrossings	# of Undercrossings	Length Miles	Year Built / Installed	Current Age	Condition	Priority	7/2003-6/2004	7/2004-6/2005	9002/9/2002/2	7/2006-6/2007	7/2007-6/2008	5 Year Projection
	3% Annual Inflation Adjustment																
1	Alder Creek Trail - Existing	L&L				1	0.66		3	Good	0						
	Proposed Trails / Structures						0.00	0									
	Sub Total						0.66										
2	American River Bikeway (State Parks) - Existing	State Parks Maintained				3	7.60			Good	0						
	Proposed Trails / Structures	State Farks Maintaineu	_			3	0.32	2004	0	0000	0						
	Sub Total						7.92	2001									
3	Baldwin Dam Trail - Existing	L & L Maintained					0.71	1995		Poor	0						
	Proposed Trails / Structures						0.25	2005	0								
	Sub Total						0.96										
4	Broadstone 2 Trail - Existing	L & L Maintained	1				1.10	2000	3	Good	0						
4	Proposed Trails / Structures						0.00	0	J	0000							
	Sub Total						1.10	- U									
5	Oak Parkway Trail (South) - Existing	L & L Maintained	1				1.58	1999	4	Good	0						
	Proposed Trails / Structures						0.22	2006	0								
	Sub Total						1.80										
6	Broadstone 3 Trail - Existing	HOA / L & L Maintained				3	3.37	2002	1	New	0	_					
0	Proposed Trails / Structures	nog i e a e maintaineu				3	3.21	2002	0	INGW	J						
	Sub Total						6.58	2000									
7	City Park Trail - Existing	City Maintained					0.10	1995	8	Good	7						
	Proposed Trails / Structures						0.00	0									
	Sub Total						0.10					_		\$2,719			\$2,719
8	East Lake Natoma Trail (State Parks) - Existing	State Parks Maintained	_		1		4.60	2000	2	New	0						
0	Proposed Trails / Structures	State Parks maintained					4.60	2000	3	IN6M,	0						
	Sub Total						4.86	2003									
							1.00										
	1								1	1							

Department Summary

	RENOVATION MASTER PLAN 2003						00/00 07/00
	Total Cost Projections						02/03 - 07/08
Sheet Number	Division Name	7/2003-6/2004	7/2004-6/2005	7/2005-6/2006	7/2006-6/2007	7/2007-6/2008	5Yr Projection
1	PARKS						
	Total Annual Projection	\$1,882,502	\$165,340	\$78,433	\$272,516	\$27,650	
	5 Year Projections						\$2,426,442
2	FACILITIES						
	Total Annual Projection	\$97,000	\$0	\$0	\$384,225	\$24,041	
	5 Year Projections						\$505,266
3	AQUATICS CENTER						
	Total Annual Projection	\$0	\$0	\$0	\$0	\$0	
	5 Year Projections						\$0
4	TRAILS						
	Total Annual Projection	\$0	\$51,665	\$107,459	\$0	\$93,677	
	5 Year Projections						\$252,800
	TOTAL PROJECTION						
	Total Annual Projection	\$1,979,502	\$217,005	\$185,892	\$656,741	\$145,368	
	5 Year Projections						\$3,184,508

Why have trails?

- Improved Quality of Life
- Safety
- Recreating
- Exercise
- Healthy Lifestyle
- Healthy Body is a Healthy Mind
- Obesity & Diabetes Prevention
- Camaraderie (Group rides)
- Wildlife Viewing
- Habitat Restoration
- ADA Accessibility
- Property Values +
- Serenity
- FUN!!!

Good times on the trails...







Cont...





See YOU on the Trails!!!

